

August 12, 2016

Project: Sycamore Forest Preserve Improvements

LETTING: 10:00 a.m., August 17, 2016 DeKalb County Highway
Department

**** PLEASE FORWARD ON TO AFFECTED SUBCONTRACTORS AND ALL AFFECTED PARTIES IN
YOUR COMPANY****

ADDENDUM NOTICE #2 TO PROSPECTIVE BIDDERS

The following serves as an addendum notice for the project. This information supersedes all conflicting information contained within the plans and specifications. All contractors must use the information in completing their bids.

Posted August 12, 2016

1. Plan sheet page 4 of 9 – The Variable Depth HMA Surface Removal Butt Joint areas (totaling 497 Sq, Yds) are included in the plan quantity for Pavement Removal. Remove references to “Incidental” for these locations. The locations are along the south side of the project along IL Route 64.

Also, the following is to serve as additional information for bidders:

1. The seeding and reasonable restoration of the access route to the compensatory storage area and the area itself will be completed by others. The contractor shall smooth out any high spots and fill ruts in these areas left by their operations. This work shall not be paid for separately but considered included in the unit price bid for Earth Excavation. Any additional excavation or topsoil placement requested by the Forest Preserve District shall be paid for separately.
2. The existing sidewalk is intended to be used as roadway base unless included in areas of pavement removal or pavement patching. Existing curbs along the entrance drives are to remain.
3. The existing large boulder rocks currently serving as a vehicle barrier on or surrounding the work shall be moved before construction by others.
4. The plan quantity for locations for Top Soil Furnish and Place, 4” include areas shown on the plans of aggregate or bituminous pavement removal and the slopes for the path connection ramp at the northeast corner.

5. Areas for the aggregate lot removal shown on plan Sheet 4 total 504 Sq. Yds. and are noted as "FULL DEPTH AGGREGATE REMOVAL, RESTORE WITH TOP SOIL AND SEED, TYP. INCIDENTAL TO TOP SOIL FURNISH & PLACE – 4". The quantities for seeding and topsoil placement are included with the plan quantities of Seeding Class 1A Complete and Top Soil Furnish and Place, 4". The location is on the southeast corner of the property.
6. The full depth aggregate removal indicated on sheet 4 shall be limited to 6 inches of depth maximum from the existing ground surface.
7. Clearing of the existing road prior to priming shall be performed in accordance with Article 406.05b(1). This work shall not be paid for separately but considered included in the unit price bid for Bituminous Materials (Prime Coat)
8. Areas where the proposed EOP departs from the existing EOP shall be covered with the aggregate shoulders paid for with the contract. The proposed surfacing will follow the existing edge of pavements on the loop drives.
9. A portion of fence to be removed is located at the northeast corner of the project. Total length of removal shall be less than 30 feet. This work shall not be paid for separately but considered included in the unit price bid for Earth Excavation.

Thank you,

Scott A. Brown, P.E.,S.E. | Director

Wendler Engineering Services, Inc. | www.wendlergs.com

698 Timbercreek Road | Dixon, Illinois 61021

815.288.2261 office | 815.973.1444 mobile | 815.288.7847 fax | sbrown@wendlergs.com